American River Flood Control District Facilities Roof Replacement – Design Drawings Staff Report

Discussion:

The District worked with Lionakis architects in 2015 to design and construct a new headquarters office facility. At the time of the project, certain measures were taken to reduce overall construction costs. One of the items that was left out of the work was the installation of a new roof. The estimate at the time was that the existing roof had 2 to 3 more years of service life before needing to be replaced. The useful service life of the roof on the headquarters building has now been exceeded. Numerous leaks have been detected and are starting to cause damage to ceiling tiles and other structures.

District staff contacted Lionakis to help us develop a design for a new roof and also to generate bid documents to issue to a roofing contractor. During discussions with Lionakis, staff requested that they also include options for adding additional roof ventilation in the warehouse.

The Board of Trustees approved a contract with Lionakis to develop the roof designs and bid documents in September 2019. Staff worked with the Lionakis design team to identify components of the roof design needed for the District facility. Central to the effort was the correction of numerous drainage deficiencies in the existing roof.

Lionakis completed the final design drawings for the roof replacement and is submitting them to the Board of Trustees for approval. Upon approval, Lionakis will submit the drawings to the City of Sacramento permitting department for plan check and then develop bid documents for approval at a subsequent Board meeting.

Costs estimates by division for the roof replacement are as follows:

General Requirements	\$93,033
Existing Conditions	\$138,293
Electrical Demolition	\$1,509
Concrete and Masonry	\$19,574
Metal Fabrication and Sheetmetal	\$19,328
Rough Carpentry	\$5,535
Framing	\$6,991
Sheathing	\$10,000
Thermal Insulation	\$2,559

Roofing Membrane` Doors Windows Plumbing HVAC HVAC-Duct Electrical Raceway and Boxes Low Voltage Distribution Distribution Antenna Pipe	\$199,653 \$1,878 \$1,143 \$3,574 \$16,318 \$14,097 \$1,613 \$305 \$1,453 \$6,745 \$493 \$10,524	
Subtotal	\$554,618	\$554,618
Material Sales Tax Small Tools & Equip Contingency: % Est Cost Overhead: General Admin	\$16,506 \$4,427 \$57,555 \$37,986	
	\$116,474	\$671,092
Margin: GC on bid Bond: Payment & Performance	\$76,123 \$14,015	_
	\$90,138	\$761,230
Total	\$761,230	

Recommendation:


The General Manager recommends that the Board approve the final roof designs from Lionakis.


AMERICAN RIVER FLOOD CONTROL DISTRICT


185 COMMERCE CIRCLE SACRAMENTO, CA 95815

RE-ROOF & MECHANICAL WORK


SUBMITTAL SET DECEMBER 16, 2019









ROOF PLAN LEGEND










6 NORTH EXTERIOR ELEVATION

SCALE 1/16" = 1'-0"






8 SOUTH EXTERIOR ELEVATION
SCALE 1/16" = 1'-0"




(E) DRAIN MODIFICATION AT ELECT.



(E) SCUPPER / OVERFLOW INFILL

3" = 1'-0"



WINDOW & DOOR LOUVER VENT LOCATIONS



UNIT B



DEMO EXISTING HVAC UNIT, PIPE & CONDUITS, AND DUCT WORK. PATCH HOLES IN (E) ROOF & PREP FOR INSTALLATION OF NEW UNIT WITH NEW PIPE, CONDUIT & DUCT PENETRATIONS.



UNIT A



UNIT A EXISTING HVAC UNIT, PIPE, & CONDUIT PENETRATIONS TO REMAIN

(E) HVAC UNITS



SEAL

CASSO CALIFORNIA

PROJECT

185 COMMERCE CIRCLE SACRAMENTO, CA 95815

165 COMMERCE CIRCLE. SUITE D, SACRAMENTO, CA 95815

ISSUED		
MARK	DATE	DESCRIPTION

MANAGEMENT

LIONAKIS PROJECT NO: 019134

CLIENT PROJECT NO: LIONAKIS 2019


AGENCY


TITLE ELEVATIONS -


EXTERIOR

A-211


UNITS A-2









TYP SAWCUT OF OPENING IN (E) CONC SLAB / WALL FOR NEW SCUPPERS



18) INFILL FRAMING AT PATCHED OPENINGS




OPENING IN (E) FRAMING @ NEW EXHAUST FANS 3/4" = 1'-0"



NOTES:
1. FRAMING IS DOUGLAS FIR-LARCH NO. 1 AND BETTER.
2. ATTACH FRAMING MEMBERS WITH "SIMPSON" U HANGER EACH END.

PLAN DETAIL - NEW MECH. UNIT





ISSUED

DESCRIPTION

MARK DATE

165 COMMERCE CIRCLE. SUITE D, SACRAMENTO, CA 95815

MANAGEMENT

LIONAKIS PROJECT NO: 019134

CLIENT PROJECT NO: LIONAKIS 2019

AGENCY

DETAILS - STRUCTURAL

A-512

Page 8

$\overline{}$
o
$\overline{}$
0
∹
<u>~</u>
Φ
ਨ
$\tilde{}$
$\stackrel{\sim}{}$
2
=
_
0
⇌
ပ
\neg
ᅙ
$\tilde{}$
\simeq
Δ.
_
4
0
€
$\dot{\circ}$
\simeq
\simeq
g-E
w
n
4
$\overline{}$
RFCD
O
屲
=
œ
$\overline{}$
~
⇁
ñ
<u>`</u>
⋋
O,
↽
0
\leq
\circ
$\overline{}$
1019\019134 ARFCD
L:\2019\(
~
· i
_

	MECHANICAL LEGEND						
SYMBOL	DESCRIPTION						
	— DETAIL NUMBER						
	SHEET ON WHICH DETAIL IS FOUND						
$\xrightarrow{\mathbb{R}}$	DUCT RISE						
$\xrightarrow{\hspace{1cm} \mathbb{D} \hspace{1cm} \stackrel{\checkmark}{\longrightarrow} \hspace{1cm}}$	DUCT DROP						
————→ OŚA	OUTSIDE AIR						
———> SA	SUPPLY AIR						
$\longrightarrow RA$	RETURN AIR						
BD	BALANCE DAMPER						
Ø	DIAMETER OR PHASE						
~~~~	FLEXIBLE DUCT						
12×10 12×10L	DUCT - DIMENSION SHOWN X WIDTH OR HEIGHT NOT SHOWN						
	ACOUSTICAL LINED DUCTING						
	DUCT TRANSITION  GURBELY AIR DIFFUSER RETURN OR EXHAUST AIR CRILLE						
	SUPPLY AIR DIFFUSER, RETURN OR EXHAUST AIR GRILLE THERMOSTAT						
R	RELOCATE						
MD	MOTORIZED DAMPER						
$\longrightarrow$ $\times$ $\times$	EXISTING PIPING OR FIXTURE TO BE REMOVED OR ABANDONED IN PLACE						
POC	POINT OF CONNECTION						
ABC	ABOVE CEILING						
AE	AIR EXTRACTOR						
AFF	ABOVE FINISHED FLOOR						
AFG	ABOVE FINISHED GRADE						
AP	ACCESS PANEL						
UCD	UNDER CUT DOOR						
CD	CONDENSATE DRAIN						
CFM, £	CUBIC FEET OF AIRFLOW PER MINUTE						
CLG.	CEILING						
(E), EXISTING	EXISTING TO BE FIELD VERIFIED BY CONTRACTOR						
FA, TA FB, TB	FROM ABOVE, TO ABOVE FROM BELOW, TO BELOW						
FD, 1D FC	FLEXIBLE CONNECTION						
F.F.	FINISHED FLOOR						
FSD	FIRE SMOKE DAMPER						
/FT	PER FOOT						
(N)	NEW						
NIMC	NOT IN MECHANICAL CONTRACT						
N.T.S.	NOT TO SCALE						
0.B.D.	OPPOSED BLADE DAMPER						
REF	REFERENCE						
(SD)	SMOKE DETECTOR						
TYP.	TYPICAL						

	PLUMBING LEGEND
SYMBOL	DESCRIPTION
	SOIL, WASTE OR SANITARY SEWER BELOW GRADE OR SLAB
GW	GREASE WASTE BELOW GRADE
—— ДШ ———	ACID WASTE
	SOIL, WASTE OR SANITARY SEWER ABOVE GRADE OR SLAE
	VENT PIPING
	COLD WATER PIPING
	HOT WATER PIPING
	HOT WATER RETURN PIPING
—— G ——	GAS PIPING - PRESSURE NOTED
—— CA ——	COMPRESSED AIR PIPING
—— FS ———	FIRE SPRINKLER PIPING
SD	STORM DRAIN PIPING
P\$TR	PRESSURE AND TEMPERATURE RELIEF PIPING
CD	CONDENSATE DRAIN PIPING
<del></del>	UNION
—√— <h 50v<="" td=""><td>SHUT OFF VALVE</td></h>	SHUT OFF VALVE
→>> GY	GATE VALVE
—————————————————————————————————————	GATE VALVE IN VALVE BOX
- CKY	CHECK VALVE - DIRECTION OF FLOW INDICATED
——————————————————————————————————————	BALL VALVE
	AUTOMATIC GAS SHUT-OFF VALVE
P#TRY	PRESSURE AND TEMPERATURE RELIEF VALVE
——	GRADE CLEAN OUT, FLOOR CLEAN OUT
← CO, WCO	CLEANOUT, WALL CLEANOUT
— FD	FLOOR DRAIN
F5 F5	FLOOR SINK
——+ HB	HOSE BIBB
<del>     </del>	POINT OF CONNECTION
POD	POINT OF DISCONNECT
I.E.	INVERT ELEVATION
US,UF,UG	UNDER SLAB, UNDER FLOOR, UNDERGROUND
V, VR, VTR	VENT, VENT RISER, VENT THRU ROOF
55	SANITARY SEWER
HW, HWD, HWR	HOT WATER, HOT WATER DROP, HOT WATER RISER
CW, CWD, CWR	COLD WATER, COLD WATER DROP, COLD WATER RISER


#### **GENERAL MECHANICAL NOTES**


- ALL EQUIPMENT AND MATERIALS SHALL BE NEW AND SHALL BE EQUAL IN QUALITY, TYPE, CAPACITY EFFICIENCY AND ACCESSORIES TO THE EQUIPMENT NOTED ON THE DRAWINGS. ADJUSTMENTS TO CONSTRUCTION AND ACCESSORIES ON SUBSTITUTED EQUIPMENT MAY BE REQUIRED TO ACHIEVE THIS EQUALITY, AND SHALL BE INCLUDED AT NO EXTRA COST TO THE OWNER. MAKE ANY CHANGES IN DUCTWORK, PIPING, FRAMING, ETC., AS REQUIRED TO ACCOMMODATE SUBSTITUTED EQUIPMENT.
- INSTALL ALL EQUIPMENT AND MATERIALS AND PERFORM ALL WORK IN ACCORDANCE WITH ALL APPLICABLE CODES. APPLICABLE CODES SHALL INCLUDE, BUT NOT BE LIMITED TO THE 2019 CALIFORNIA MECHANICAL CODE, 2019 CALIFORNIA CODE OF REGULATIONS (CCR), 2019 CALIFORNIA FIRE REGULATIONS, 2019 CALIFORNIA GREEN BUILDING STANDARDS AND 2019 CALIFORNIA TITLE 24 ENERGY EFFICIENCY STANDARDS. WHERE HEAVIER GAGES OF MATERIAL, LARGER SIZES OR MORE STRINGENT REQUIREMENTS THAN THE CODES ARE REQUIRED BY THE CONTRACT DOCUMENTS, SUCH INCREASED REQUIREMENTS SHALL APPLY.
- FABRICATE AND INSTALL ALL DUCTWORK IN ACCORDANCE WITH THE LATEST EDITION OF SMACNA GUIDELINES FOR DUCT CONSTRUCTION AND THE 2016 CALIFORNIA MECHANICAL CODE. ALL DUCT JOINTS INCLUDING MECHANICAL FLANGED JOINTS SHALL BE SEALED WITH SILVER TAPE, OR ARABOL AND CANVAS. SEAL THE JOINTS OF ALL DUCTS EXPOSED TO THE WEATHER WITH ARABOL AND CANYAS. PROVIDE ALL BRANCH DUCTS WITH YOLUME DAMPERS WITH LOCKING QUADRANTS LOCATED AT LEAST FIVE FEET (5') FROM THE GRILLE OR DIFFUSER SERVED.
- 4. SUPPORTS FOR ALL PIPING AND DUCTWORK SHALL BE IN ACCORDANCE WITH SMACNA "GUIDELINES FOR SEISMIC RESTRAINT OF MECHANICAL SYSTEMS". CONTRACTOR SHALL PROVIDE CALCULATIONS FOR ISOLATORS AND MOUNTING ACCEPTABLE TO THE REVIEWING AUTHORITY WHEN REQUIRED BY SAME.
- ALL RECTANGULAR OR ROUND RIGID DUCTS SHALL BE OF SMACNA GAGE GALYANIZED STEEL OR ALUMINUM, UNLESS OTHERWISE NOTED ON THE DRAWINGS. PROVIDE FLAT SEAM CONSTRUCTION FOR ANY DUCTS EXPOSED IN OCCUPIED SPACE. NOTE: ALUMA-FLEX IS NOT ACCEPTABLE IN LIEU OF ROUND RIGID <u>DUCTWORK.</u>
- 6. FLEXIBLE DUCTS WHERE PERMITTED SHALL BE GENFLEX IL, THERMAFLEX G-KM, CASCO OR EQUAL FACTORY INSULATED. FLEXIBLE DUCT SHALL NOT EXCEED 5-0" IN LENGTH (DOWNSTREAM OF RIGID ELBOWS), PER 2016 CMC, 603.4.1 INSULATE ALL SUPPLY AND RETURN DUCTS WITH 2" THICK, 3/4 PCF DENSITY O-C F OR EQUAL, FIBERGLASS DUCT WRAP, TYPE IV, WITH FACTORY APPLIED FLAME RETARDANT FOIL REINFORCED KRAFT FACING. LAP ALL JOINT 4" MINIMUM, AND SECURE WITH GALYANIZED STEEL WIRE.
- 7. LINE ALL SUPPLY AND RETURN DUCT DROPS FOR A MINIMUM OF 10' FROM THE UNIT WITH I" THICK O-C F AEROFLEX TYPE 200 OR EQUAL ACOUSTIC DUCT LINER. INSTALL WITH 100% COVERAGE ADHESIVE, AND FURTHER APPLY MECHANICAL PIN FASTENERS WHERE DUCT SIDE EXCEEDS 24". DUCT DIMENSIONS ARE NET INTERNAL DIMENSION, SEAL BUTT ENDS OF EXPOSED INSULATION IN THE DUCTS WITH MANUFACTURERS RECOMMENDED SEALANT OR ADHESIVE.
- CONTROLS SHALL COMPLY WITH THE 2016 CALIFORNIA ENERGY CODE. ALL CONTROLS AND CONTROL WIRING NOT SPECIFICALLY SHOWN BUT REQUIRED FOR A COMPLETE AND WORKABLE SYSTEM SHALL BE SUPPLIED BY THE CONTRACTOR AND INSTALLED AT NO ADDITIONAL COST TO THE OWNER.
- ALL AIR SYSTEMS SHALL BE BALANCED BY A QUALIFIED MECHANICAL CONTRACTOR, USING AABC, SMACNA OR NEBB PROCEDURES. AIR QUANTITIES SHALL BE BALANCED TO NOT MORE THAN 10% ABOVE OR 10% BELOW THE QUANTITIES SHOWN ON THE DRAWINGS. CONTRACTOR SHALL SUBMIT A COMPLETE AIR BALANCE REPORT INDICATING, AS A MINIMUM, THE AIR DELIVERY FOR EACH DIFFUSER, THE FINAL OPERATING DATA FOR THE SYSTEMS AND THE AIR CONDITIONING UNITS.
- 10. SUBMIT FOR APPROVAL (6) COPIES OF COMPLETE SUBMITTAL DATA ON SPECIFIED AND PROPOSED EQUIPMENT AND MATERIALS. SUBMITTALS SHALL INCLUDE EQUIPMENT SIZES, CAPACITY, MOTOR LOCATIONS, PERFORMANCE CURVES AND OTHER PERTINENT DATA. EACH SUBMITTAL SHALL INCLUDE IDENTIFICATION TAGS OR SYMBOLS TO MATCH DWGS. PARTIAL SUBMITTALS OR SUBMITTALS WHICH ARE NOT MARKED WITH EQUIPMENT TAGS OR PERFORMANCE DATA WILL BE REJECTED.
- PROVIDE PERMANENT ENGRAVED PLASTIC NAME PLATED FOR ALL EQUIPMENT INSTALLED, INDICATING THE PLAN DESIGNATION OF THE UNIT (AC-1, REF., ETC.) AND ALSO THE BUILDING AREA SERVED (CLASSROOMS 2-4, CONFERENCE ROOM, ETC.). STAMPED METAL TAPES APPLIED WITH SELF-CONTAINED ADHESIVE WILL NOT BE ACCEPTABLE.
- 12. CONTRACTOR SHALL VERIFY ALL WORK CONDITIONS PRIOR TO COMMENCING WORK, INCLUDING, BUT NOT LIMITED TO: DIMENSIONS, EQUIPMENT, STRUCTURAL ELEMENTS AND MATERIALS INDICATED AS EXISTING, AS WELL AS THE COORDINATED INSTALLATION OF ALL NEW WORK, MATERIALS, EQUIPMENT, ETC. COORDINATE THE LOCATION OF ALL ROOF MOUNTED EQUIPMENT WITH THE STRUCTURAL ENGINEER.
- 13. CONTRACTOR SHALL FIELD COORDINATE AND INSTALL PACKAGED ROOFTOP EQUIPMENT TO MAINTAIN A MINIMUM OF 10'-0" CLEARANCE FROM OUTSIDE AIR INTAKE TO ALL EXHAUST OUTLETS AND (VTR) VENT THRU ROOF, TYPICAL.
- 14. <u>SUBMITTAL NOTE:</u> MECHANICAL SYSTEMS DESIGN REFLECT EQUIPMENT SPECIFIED. WHEN EQUIPMENT SUBSTITUTIONS OCCUR AND DUCT DESIGN, DUCT DROPS, GAS INPUT AND ELECTRICAL SERVICE VARIES FROM THAT SPECIFIED, THEN IT SHALL BE THE RESPONSIBILITY OF THE MECHANICAL CONTRACTOR FOR ALL ADDITIONAL ENGINEERING FEES AND OTHER DISCIPLINE CHANGE ORDERS (STRUCTURAL, ELECTRICAL, ARCHITECTURAL, PLUMBING, ETC) WHEN SUBSTITUTED EQUIPMENT IS USED.


### GENERAL PLUMBING NOTES

- ALL EQUIPMENT AND MATERIALS USED SHALL BE NEW AND SHALL BE EQUAL IN QUALITY, TYPE, CAPACITY AND ACCESSORIES TO THE EQUIPMENT NOTED ON THE DRAWINGS. ADJUSTMENTS TO CONSTRUCTION AND ACCESSORIES ON SUBSTITUTED EQUIPMENT MAY BE REQUIRED TO ACHIEVE THIS EQUALITY, AND SHALL BE INCLUDED AT NO EXTRA COST TO THE OWNER. MAKE ANY CHANGES IN PIPING, FRAMING, ETC., AS REQUIRED TO ACCOMMODATE SUBSTITUTED EQUIPMENT.
- 2 INSTALL ALL EQUIPMENT AND MATERIALS AND PERFORM ALL WORK IN ACCORDANCE WITH ALL APPLICABLE CODES. APPLICABLE CODES SHALL INCLUDE, BUT NOT BE LIMITED TO THE 2019 CALIFORNIA MECHANICAL CODE, 2019 CALIFORNIA PLUMBING CODE, 2019 CALIFORNIA CODE OF REGULATIONS (CCR), 2019 CALIFORNIA FIRE CODE AND 2019 TITLE 24 ENERGY EFFICIENCY STANDARDS. WHERE HEAVIER GAGES OF MATERIAL, LARGER SIZES OR MORE STRINGENT REQUIREMENTS THAN THE CODES ARE REQUIRED BY THE CONTRACT DOCUMENTS, SUCH INCREASED REQUIREMENTS SHALL APPLY.
- 3. PIPING MATERIALS SHALL BE AS FOLLOWS: CONDENSATE DRAIN PIPING: TYPE DWY COPPER TUBING AND FITTINGS OR SCHEDULE 40 GALVANIZED STEEL PIPE AND MALLEABLE IRON FITTINGS. (PYC PIPING WILL NOT BE ACCEPTABLE.)
- 4. CONTRACTOR SHALL VERIFY ALL WORK CONDITIONS, PRIOR TO COMMENCING WORK, INCLUDING, BUT NOT LIMITED TO: PIPING SIZES, INVERT ELEVATIONS, POINTS OF CONNECTION, FIXTURES AND EQUIPMENT, STRUCTURAL ELEMENTS AND MATERIALS INDICATED AS EXISTING, AS WELL AS THE COORDINATED INSTALLATION OF ALL NEW WORK, MATERIALS, EQUIPMENT, ETC. VERIFY THE LOCATION AND REQUIRED PIPING CONNECTIONS OF ALL HYAC OR OTHER MECHANICAL EQUIPMENT, NOTIFY ARCHITECT OF ANY DISCREPANCIES PRIOR TO TRENCHING OR COMMENCING OTHER

SYMBOL	DESCRIPTION
	COOLING CAPACITIES ARE BASED AT 95° F. AMB., 80° F. DB, 61° F. WE ENTERING AIR TEMPERATURE. HEATING CAPACITIES ARE BASED AT 30° F.
	PACKAGED ROOFTOP AIR-CONDITIONING UNIT WITH ELECTRIC COOLING AND HEATING, VERTICAL DISCHARGE, R-410A REFRIGERANT. FURNISH COMPLETE WITH ROOF CURB, BELT-DRIVE MOTOR, FULLY MODULATING 100% OUTSIDE AIR ECONOMIZER WITH MODULATING POWER EXHAUST, COMPRESSOR SHORT CYCLE PROTECTOR, THERMOSTAT, DISPOSABLE FILTERS IN FILTER RACK. POWER EXHAUST OPERATION BY SPACE MOUNTED STATIC PRESSURE SENSOR.
HP 1	TRANE MODEL NO.: WSC090 OR EQUAL, II.I SEER, NOMINAL 7.5 TON UNIT TOTAL COOLING CAPACITY: 94,000 BTUH SENSIBLE COOLING CAPACITY: 69,300 BTUH INSTANTANEOUS HEATING CAPACITY: 36,300 BTUH INTEGRATED HEATING CAPACITY: 31,800 BTUH AIR FLOW SETTING: 3000 CFM AT 0.8 S.P. ELECTRICAL SERVICE: 208 V/3 Ph/60 Hz COMPRESSOR: I AT 19.1 RLA, 128 LRA EVAPORATOR FAN MOTOR: I AT 1.0 HP, 7.9 FLA CONDENSER FAN MOTOR: I AT 2 FLA, 6.6 LRA MCA: 38.4 MOCP: 60 1062 LBS.
REF	ROOF EXHAUST FAN LOREN COOK MODEL NO.: 195CITD (VF2) OR EQUAL. AIR FLOW SETTING: 4,000 CFM AT 0.15 S.P., 1725 RPM ELECTRICAL SERVICE: 208 V/3 Ph/60 Hz, EC FAN MOTOR: 5 HP, 3.98 BHP CONTROL WITH WALL SWITCH, THERMOSTATIC SWITCH, CO SENSOR SWITCH. WEIGHT: 218 LBS. SOUND LEVEL: 43 SONES FURNISH: ROOF CURB, BIRD SCREEN, BACK DRAFT DAMPER, DISCONNECT SWITCH, INHERENT MOTOR PROTECTION.
REF REF	ROOF EXHAUST FAN LOREN COOK MODEL NO.: 180C17D (VF2) OR EQUAL. AIR FLOW SETTING: 5,500 CFM AT 0.15 S.P., 1542 RPM ELECTRICAL SERVICE: 208 V/3 Ph/60 Hz, EC FAN MOTOR: 3 HP, 1.83 BHP CONTROL WITH WALL SWITCH, THERMOSTATIC SWITCH, CO SENSOR SWITCH. WEIGHT: 197 LBS. SOUND LEVEL: 29 SONES FURNISH: ROOF CURB, BIRD SCREEN, BACK DRAFT DAMPER, DISCONNECT SWITCH, INHERENT MOTOR PROTECTION.








ALL ROOF PENETRATIONS TYPICAL.

ROOF EXHAUST FAN MOUNTING DETAIL SCALE: NONE



1919 Nineteenth Street Sacramento CA 95811 P 916.558.1900 F 916.558.1919 www.lionakis.com

CONSULTANT





ROOF REPAIR / REPLACEMENT

185 COMMERCE CIRCLE SACRAMENTO, CA 95815

AMERICAN RIVER FLOOD CONTROL DISTRICT 165 COMMERCE CIRCLE. SUITE D, SACRAMENTO, CA

MARK DATE DESCRIPTION


MANAGEMENT LIONAKIS PROJECT NO 019134 CLIENT PROJECT NO: LIONAKIS 2019 COPYRIGHT:

AGENCY

MECHANICAL /

PLUMBING LEGEND, NOTES, & SCHEDULES

MP1.1



- FIELD COORDINATE FAN UNIT FINAL LOCATION TO MAINTAIN MINIMUM 10 FEET FROM ALL OUTSIDE AIR INTAKE. SECURE ROOF EXHAUST FAN TO ROOF FRAMING MEMBERS AS REQUIRED. FIELD VERIFY DUCT DROP OPENING SIZES THROUGH ROOF WITH STRUCTURAL MEMBERS. DUCT TO EXTEND MINIMUM 6 INCHES BELOW ROOF INSULATION. TYPICAL.
- 2) FURNISH AND INSTALL THERMOSTATIC CONTROL ON COLUMN AS SHOWN. SET TO OPERATE FAN AT 80°F (ADJUSTABLE). TYPICAL.
- 3 FURNISH AND INSTALL CARBON MONOXIDE MONITOR ON COLUMN AS SHOWN. SET EXHAUST FAN TO OPERATE WHEN CO LEVEL REACHES 50 PPM (ADJUSTABLE) OR HIGHER. TURN FAN OFF WHEN CO LEVEL DROPS BELOW 40 PPM. CO MONITOR SHALL BE ACME UNISET MODEL (120V) FOR SINGLE GAS MONITOR. TYPICAL.
- FURNISH AND INSTALL WALL MOUNTED TIMER SWITCH AT +48" AFF FOR MANUAL ACTIVATION OF EXHAUST FAN. FIELD COORDINATE EXACT LOCATION WITH FACILITY PERSONNEL. TIMER SWITCH SHALL HAVE OPERATING RANGE FROM 15 MINUTES TO 2 HOURS MAXIMUM. TYPICAL.
- 5 FURNISH AND INSTALL OUTSIDE AIR INTAKE LOUVER AT DOOR, LOUVER SHALL HAVE MINIMUM FREE AREA AS INDICATED, LOUVER TO BE POTTORFF MODEL EAF-445 OR EQUAL, TYPICAL.
- 6 FURNISH AND INSTALL OUTSIDE AIR INTAKE LOUVER AT EXTERIOR WALL. LOUVER SHALL HAVE MINIMUM FREE AREA AS INDICATED. REMOVE EXISTING GLAZING PANEL AND INSTALL ADDITIONAL TRIM PIECES AS REQUIRED. LOUVER SHALL BE NATIONAL GUARD PRODUCTS MODEL L-700-RX OR EQUAL. TYPICAL.
- REMOVE EXISTING PACKAGED HEAT PUMP <u>HP-1</u> (7.5-TON) AND DUCT PLENUMS ON ROOF. REMOVE DUCT SMOKE DETECTOR TO BE RE-INSTALLED AT SUPPLY DUCT BELOW ROOF.
- SECURE NEW ROOFTOP HEAT PUMP UNIT (HP-1) TO ROOF FRAMING MEMBERS AS REQUIRED. FIELD VERIFY FINAL UNIT LOCATION AND DUCT DROPS THROUGH ROOF WITH STRUCTURAL MEMBERS AND EXISTING ELECTRICAL CONDUITS.
  REFER TO ARCHITECTURAL/STRUCTURAL PLAN FOR STRUCTURAL SUPPORT DETAIL.
- 9 LINED SUPPLY/RETURN AIR DUCTS DOWN THROUGH ROOF, TRANSITION WITHIN ROOF CURB AND/OR UNDERSIDE OF ROOF STRUCTURE TO EXISTING SA/RA DUCT MAINS, CONNECT DUCT TO UNIT COMPLETE WITH FLEXIBLE CONNECTION, TYPICAL.
- ONNECT EXISTING TRANE VARITRAC CENTRAL CONTROL PANEL (CCP) TO NEW HP-1 TO PERFORM BYPASS/ZONE FUNCTIONS PER TRANE PROTOCOL.
- (I) ROUTE CONDENSATE DRAIN PIPING DOWN THRU ROOF AND CONNECT TO EXISTING DRAIN PIPING AT UNDERSIDE OF ROOF, FIELD COORDINATE EXACT ROUTING AND POINT OF CONNECTION.

WHEN EXHAUST FAN IS NOT CONTROLLED BY TIMER SWITCH, IT SHALL BE ACTIVATED EITHER BY CO MONITOR OR THERMOSTATIC CONTROL.

MECHANICAL CONTRACTOR SHALL PROVIDE TIMER SWITCH, CO MONITOR, AND THERMOSTATIC CONTROL, ALL TO BE INSTALLED BY ELECTRICAL CONTRACTOR. ELECTRICAL CONTRACTOR SHALL FURNISH ANY RELAY AND/OR CONTACTOR AS REQUIRED TO PERFORM ALL THREE FUNCTIONS OF EXHAUST FAN OPERATION. TYPICAL.

ISSUED

MARK DATE DESCRIPTION

Sacramento CA 95811

www.lionakis.com

CONSULTANT

P 916.558.1900 F 916.558.1919

www.saceng.com

ROOF REPAIR / REPLACEMENT

185 COMMERCE CIRCLE SACRAMENTO, CA 95815

AMERICAN RIVER FLOOD CONTROL DISTRICT

165 COMMERCE CIRCLE. SUITE D, SACRAMENTO, CA

Job No. 19686

MANAGEMENT

LIONAKIS PROJECT NO: 019134

CLIENT PROJECT NO: LIONAKIS 2019

AGENCY

TITLE

MECHANICAL / PLUMBING PLAN


MP2.1

MECHANICAL/PLUMBING PLAN
SCALE: 1/8"=1'-0"

RE-INSTALL (E)

6x14 BEAM

SMOKE DETECTOR



SCALE: 1/4"=1'-0"

(E) MOTORIZED

(E)18×22L RA

ENLARGED MECHANICAL PLAN

ELEC. CONDUIT

6x2Ø BEAM

I\

A.F.F. ABOVE FINISHED FLOOR PRI. PRIMARY PYC POLYVINYL CHLORIDE ALUMINUM B.C. BARE COPPER CONDUIT CONDUIT SEC. SECONDARY C.O. CONDUIT ONLY, WITH PULL TTB TELEPHONE TERMINAL BOARD LINE TTC TELEPHONE TERMINAL CABINET COPPER RECEPTACLE SUBSCRIPTS: TYP. TYPICAL (E) EXISTING UG UNDERGROUND EMT ELECTRICAL METALLIC UON UNLESS OTHERWISE NOTED TUBING y yolts GND. GROUND WP WEATHERPROOF EXHAUST FAN, N.I.E.S., CONNECT AS REQUIRED H.I.D. HIGH INTENSITY DISCHARGE W WIRE J-BOX JUNCTION BOX WP WEATHERPROOF KYA KILO YOLT AMP W/ WITH MH METAL HALIDE XFMR TRANSFORMER MSB MAIN SWITCHBOARD φ PHASE WIRE AND CONDUIT LEGEND CONDUIT RUN CONCEALED IN WALL OR ABOYE CEILING. _____ CONDUIT RUN UNDERFLOOR OR UNDERGROUND. HOME RUN, NUMBER OF ARROWS INDICATE NUMBER OF CIRCUITS IN HOME RUN. FLEXIBLE CONDUIT FACTORY WHIP NO CROSSBARS ON CONDUIT INDICATE 1/2" CONDUIT WITH TWO #12 AWG CONDUCTORS, CROSSBARS INDICATE NUMBER OF #12 AWG CONDUCTORS IN CONDUIT. CONDUCTOR SIZE OTHER THAN #12 NOTED ON DRAWING. CONDUIT SIZE OTHER THAN  $\frac{1}{2}$ " NOTED ON DRAWING. CONDUIT UP. #10 #10 EXAMPLE: THREE CIRCUITS IN HOME RUN - FOUR #10 AWG CONDUCTORS AND ONE #10 AWG GROUNDING CONDUCTOR 34" C. IN 34" CONDUIT, RUN CONCEALED IN WALL OR ABOVE CEILING. NUMBERED NOTES 1 > (E) WEATHER DUPLEX RECEPTACLE TO REMAIN. MOUNT TO NEW HEAT PUMP. 2 PROVIDE NEW FUSED DISCONNECT SWITCH AND RECONNECT TO (E) CIRCUIT. 25% LARGEST MOTOR 1.5 KVA 44.4 KVA / 0.360 FACTOR = 123 AMPS

-(E) PANEL 'A'

ELECTRICAL PLAN
SCALE: 1/8" = 1'-0"

**ELECTRICAL SYMBOLS** 

NON-FUSED DISCONNECT SWITCH, SIZE AS REQUIRED

ABBREVIATIONS LIST

AMPERE

√<u>A-31,33,35</u>

NTS NOT TO SCALE

FUSED DISCONNECT SWITCH WITH TIME DELAY FUSES SIZED E' PER UNIT NAMEPLATE OR AS NOTED. DISCONNECT SHALL

ACCEPT MAXIMUM RECOMMENDED FUSE SIZE.

DUPLEX RECEPTACLE, NEMA 5-15R, +18" UON

R = ROOF MOUNTED, WEATHERPROOF (IN-USE), GFCI

 $\bigcirc$   $\bigcirc$  JUNCTION BOX, SIZE AND TYPE AS REQUIRED

SWITCHBOARD, SEE ONE LINE DIAGRAM

BRANCH CIRCUIT PANEL, SEE PANEL SCHEDULES

IDENTIFICATION TAG FOR EQUIPMENT PROVIDED BY M.C. CONNECT EQUIPMENT AS INDICATED OR AS REQUIRED.

NUMBERED NOTE TAG - SEE NUMBERED NOTES, SAME SHEET

INDICATES DETAIL "A" AT SHEET "EI"

<u> 4-37,39,41</u>

EXISTING			120/2	08V. 3	Ph. 4V	٧.				
PANEL 'A'										SURFACE MOUNTED
	225 AMP BUS 10,000 ISC									
DESCRIPTION	KVA	BKR	CKT	Ph. A	Ph. B	Ph. C	CKT	BKR	KVA	DESCRIPTION
(E) RECEPTACLES	1.1	20/1	1	1.3			2	20/1	0.2	(E) FACP
(E) RECEPTACLES	0.7	20/1	3		0.9		4	20/1	0.2	(E) FIRE BELL
(E) RECEPTACLES	0.7	20/1	5			1.2	6	20/1	0.5	(E) TELE. RECEPT.
(E) RECEPTACLES	0.7	20/1	7	0.9			8	20/1	0.2	(E) ROOF RECEPT.
(E) RECEPTACLES	0.7	20/1	9		0.9		10	20/1	0.2	(E) SMOKE DAMPER
(E) RECEPTACLES	0.7	20/1	11			0.9	12	20/1	0.2	(E) ROOF RECEPT.
(E) RECEPTACLES	1.1	20/1	13	2.6			14	20/1	1.5	(E) DRYER
(E) RECEPTACLES	0.7	20/1	15		2.2		16	20/1	1.5	(E) DRYER
(E) G.D.	0.6	20/1	17			1.5	18	20/1	0.9	(E) RECEPTACLES
(E) RECEPTACLES	0.7	20/1	19	1.9			20	20/1	1.2	(E) DOOR
(E) RECEPTACLES	1.1	20/1	21		2.3		22	20/1	1.2	(E) DOOR
(E) RECEPTACLES	0.9	20/1	23			2.1	24	20/1	1.2	(E) DOOR
(E) WASHER	1.5	20/1	25	1.5			26	20/1		
(E) WH RECEPT.	0.4	20/1	27		0.4		28	20/1		
ROOF RECEPTACLES	0.5	20/1	29			0.5	30	20/1		
	1.3		31	1.3			32	20/1		
REF-2	1.3	20/3	33		3.3		34		2.0	
	1.3		35			3.3	36	30/3	2.0	REF-1
	1.3		37	3.3			38		2.0	
REF-3	1.3	20/3	39		5.3		40	50/2	4.0	(E) WATER HEATER
	1.3		41			5.3	42		4.0	
SUBTOTAL:				12.8	15.3	14.8				
CONNECTED LOAD	42.9	KVA		•					MAIN	LUGS ONLY

1919 Nineteenth Street Sacramento CA 95811 P 916.558.1900 F 916.558.1919 www.lionakis.com

CONSULTANT





ROOF REPAIR / REPLACEMENT

185 COMMERCE CIRCLE SACRAMENTO, CA 95815

AMERICAN RIVER FLOOD CONTROL DISTRICT 165 COMMERCE CIRCLE. SUITE D, SACRAMENTO, CA 95815

MARK DATE DESCRIPTION

MANAGEMENT LIONAKIS PROJECT NO CLIENT PROJECT NO: LIONAKIS 2019

**ELECTRICAL PLANS** 

E1.1